DG Pest Control & Termite

BUILDER INFORMATION
dgpesthouston.com/builders

BUILDERS & GENERAL CONTRACTORS

Termite pretreatment for Houston builders

Pre-slab soil treatment, return visits after the pour and at final grade, and Bora-Care framing treatment, scheduled around your pour and coordinated with your superintendent. For custom home builders, general contractors and owner builders.



✓ 30 years of experience ✓ Licensed & insured · TPCL #0955099 ✓ One home or repeat work ✓ Hablamos español

What DG handles on a construction project



Pre-slab soil treatment
Liquid termiticide applied to the soil under the future slab and along the foundation trenches, after the plumbing is roughed in and before the vapor barrier and pour.



After the pour and at final grade
Texas rules call for a return visit after the pour to complete the barrier, and a final treatment once landscaping is done. We schedule both.



Bora-Care framing treatment
A borate wood treatment sprayed on exposed framing before insulation and drywall, on its own or alongside a soil treatment.

Also: pest tubes inside open walls, mosquito misting systems, pest control before move-in, and slab and framing work on commercial and multifamily buildings, additions and remodels.

How a builder job runs

1. **Send the job details**
   The basics listed below. We come back with a quote.
2. **Confirm the visit**
   Tell us when the plumbing is roughed in and the forms are set. We confirm the date with you or your superintendent.
3. **Treat before the pour**
   Soil and trenches treated before the vapor barrier goes down. Then you're clear to pour.
4. **Finish the barrier**
   We come back after the slab and again at final grade, on schedule.
5. **Paperwork**
   A treatment record for your file and your buyer. Need the HUD-NPMA-99-B for an FHA or VA loan? Tell us up front.

To quote a job, send

- ✓ Job city or subdivision
- ✓ Construction stage
- ✓ Slab square footage or plans
- ✓ Expected pour window
- ✓ Number of homes or lots

Where we work

Greater Houston and the surrounding cities. Recent builder jobs: Sugar Land, Cleveland, Conroe and West University Place.

For builder projects we often travel two to four hours, after reviewing the job.

Talk to DG about your next project

346-846-3170

dg.pestcontrol@outlook.com
dgpesthouston.com/builders
Project quote form online · Hablamos español